

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,012-0000

LEASE NAME Wood E

WELL NUMBER # 2

1650 Ft. from S Section L

2970 Ft. from E Section L

SEC. 23 TWP. 26 RGE. 16 (W)

COUNTY Edwards

Date Well Completed —

Plugging Commenced 2-12-93

Plugging Completed 10:30 AM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oil Producers, Inc.

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE# (316) 672-6373 OPERATORS LICENSE NO. 8061

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-12-93 (date)

by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filled? Yes If not, is well log attached? —

Producing Formation Kinderhook Depth to Top 4409 Bottom 4488 T.D. 4535

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	490	0
				4 1/2	4531	2713

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from — feet to — feet each  
Bottom plug: Sanded to 4360 & bailed 4 sx cement.

Top plug: Pumped 300 lb Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lb Hulls, wiper plug, 125 sx Cement, 60/40 with 6% Gel. Had maximum pressure of 50 lbs & shut in pressure of 50 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License 4635 CP

Address Box 251, Great Bend, Kansas 67530 2-15-93 RECEIVED STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. FEB 15 1993

STATE OF Kansas COUNTY OF Barton, ss. CONSERVATION DIVISION Wichita, Kansas


Gary G. Burke

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 12 day of February, 1993



Anna K. Burke  
Notary Public

Expires: 4-30-96