


WELL PLUGGING RECORD 15-047-00281-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Edwards County. Sec. 12 Twp. 26S. Rge. 16 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner Leben Drilling, Inc.
Lease Name Wallace Well No. 1
Office Address 905 Central Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 5-27-63 19
Application for plugging approved 5-30-63 19
Plugging commenced 8-10-63 19
Plugging completed 9-14-63 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	285	None
				4 1/2	None	2205

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measuring T. D. Sanded to 4468'. Dumped 3 sacks of cement. Rigging up jacks. Shot well at 2500'. Working pipe. Shot well at 2318'. Working pipe. Shot well at 2200'.

Pulling pipe.

Trying to bail 8 5/8" - could not. Put over night bridge at 275'. Dumped 6 sacks of cement.

Over night bridge didn't hold. Dumped 15 sacks of cement.

Bailing and plugging well at 230'. Dumped 10 sacks of cement. Mudded to 40'. Build 10' rock bridge. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1963

9-18-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17 day of September, 19 63.

My commission expires May 27, 1964

Notary Public.

15-047-00281-0000

DRILLER'S LOG

COMPANY: Leben Drilling, Inc. & Oksaar Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: WALLACE #1
 LOCATION: C NW SW Sec. 12-26-16 EDWARDS COUNTY, KANSAS
 COMMENCED: 7-16-63
 COMPLETED: 7-27-63

0	235	Sand
235	285	Shale
285	1045	Shale & Redbed
1045	1065	Redbed & Shale
1065	1085	Anhydrite
1085	2085	Shale
2085	2270	Lime
2270	2425	Lime & Shale
2425	2555	Shale & Lime
2555	2730	Lime
2730	3060	Lime & Shale
3060	3290	Shale
3290	3707	Lime & Shale
3707	4280	Lime
4280	4342	Lime & Shale
4342	4400	Lime
4400	4425	Lime & Chert
4425	4470	Viola Lime
	<u>4470</u>	<u>Rotary Total Depth - Set 4 1/2" Casing</u>

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1963

CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" used surface casing @ 285.93' Cemented with 275 sacks of cement by Sun Oilwell Cementing, Inc.


I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wallace #1, located C NW SW of Section 12, Township 26, Range 16, Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.



Byron Johnson

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 27th day of February, 1963.



Ulanda Nichols, Notary Public

My Commission Expires:
April 1, 1963