

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 151-047-20,230-0000

LEASE NAME BEVAN WOOD

WELL NUMBER 1

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 26 RGE. 16 (N or W)

COUNTY EDWARDS

LEASE OPERATOR BEREN CORP.

ADDRESS P.O. Box 723 HAYS, KS. 67601

PHONE# 913) 628-6101 OPERATORS LICENSE NO. 5364

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced OCT 23-1992

Plugging Completed 10-27-92

The plugging proposal was approved on 10-26-92

(date)

by STEVE DURANT

(KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well-log attached?

Producing Formation Depth to Top Bottom T.D. 4510

Show depth and thickness of all water, oil and gas formations.

PERFS: 4350-4400

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	420	8 5/8	420	0
		0	4509	4 1/2	4509	1965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

10-23-92: PULLED RODS + TBG. OUT OF THE WELL.

10-24-92: DUMPED 4 BBLs. SAND DOWN WELL. 10-26-92: DUMPED 4 SX.

CEMENT ON TOP OF SAND. - TOP OF SAND AT 4260. SHOT OFF CSG. AT 1965 FT.

64 JTS. 10-29-92. TOP HOLE PLUGGED W/ 300* HULLS-10 SX GEL-50 SX

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE INC. License No. 58913

Address P.O. Box 847 PRATT, KS. 67124

STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BEREN CORP.

NOV 13 1992

STATE OF KANSAS

COUNTY OF PRATT

11-13-92
PLUGGING CONTRACTOR


JUDY BERRY

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 12th day of November, 1992

My Commission Expires February 6, 1993

Notary Public

CEMENT - 10 SX GEL - 100* HULLS - 8⁵/₈ PLUG - 125 SX
CEMENT - 60/40 POZ - 6% GEL. STEVE PFEIFER
ON LOC. FOR KCC. BJ TITAN DID THE PLUG.

