

15-047-20696-0005


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 12 Twp. 26S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW NW

Lease Owner Beren Corporation
Lease Name Bevan-Wood #2 Well No. 2
Office Address 970 Fourth Financial Center, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed November 13, 1980
Application for plugging filed November 13, 1980
Application for plugging approved November 13, 1980
Plugging commenced 4:45 PM November 13, 1980
Plugging completed 6:15 PM November 13, 1980
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4510'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	409'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 600' with 50 sacks 50/50 Pozmix with 4% gel through open ended drill pipe; heavy mud to 390' with 40 sacks through open ended drill pipe; heavy mud with solid bridge at 40; with 10 sacks to surface. 5 sacks in rathole; 5 sacks in mousehole.

NOV 16 1980
CONSERVATION DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of November, 1980.



[Signature]
Charles M. Hall, Notary Public.

My commission expires _____

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-047-20696-0000

WELL LOG - - - - - BEVAN-WOOD #2
Located: NW NW NW, Section 12-26S-16W, Edwards County,
Kansas

OWNER: Beren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 3, 1980
COMPLETED: November 13, 1980

TOTAL DEPTH: 4510'

LOG
0 - 305 Shale and Sand
305 - 1057 Shale
1057 - 1070 Anhydrite
1070 - 1875 Shale
1875 - 4427 Lime and Shale
4427 - 4430 Lime
4430 - 4510 Lime and Shale

CASING RECORD
Ran 10 joints 8 5/8" casing. 397.47'
pipe set at 409' K.B. Cemented with
325 sacks 60/40 Pozmix with 2% gel and
37 cc. Plug down at 7:45 PM, 11-3-80,
by Howco.

Plugged.

Deviation Surveys: 2° at 4100'
3/4° at 4390'

RECEIVED
NOV 13 1980
CONSERVATION DIVISION
Wichita, Kansas