

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21470-00-02
Spot: S2N2SENE Sec/Twnshp/Rge: 30-25S-18W
3481 feet from S Section Line, 650 feet from E Section Line
Lease Name: ROSPROY Well #: 1-30
County: EDWARDS Total Vertical Depth: 4695 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		WITH 2 SX CMT
CIBP		4200		
CIBP		4280		
CIBP		4350		
PROD	5.5	4693	1620	WITH 175 SX CMT
SURF	8.625	319		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/02/2015 8:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP 50' ABOVE PERFS WITH 2 SX CMT. PLUG AT 1300' WITH 50 SX CMT & 12 SX GEL. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/02/2015 11:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:
SET CIBP @ 4180' WITH 2 SX CMT. 1ST PLUG AT 1315' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 379' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4627	4638		
4232	4240		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

10/28/15 CKM

District: 01
RECEIVED
OCT 16 2015
KCC DODGE CITY

Signed Larry Harris
(TECHNICIAN)