

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21508-00-00
Spot: NENENW Sec/Twnshp/Rge: 9-26S-19W
4981 feet from S Section Line, 2971 feet from E Section Line
Lease Name: FOX B Well #: 1-9
County: EDWARDS Total Vertical Depth: 4755 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4680		WITH 2 SX CMT
CIBP		4752		
PROD 4.5		4755	1824	WITH 150 SX CMT
SURF 8.625		330		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/06/2015 8:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: GRADY THOMPSON Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: CIBP 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1300' WITH 12 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2015 10:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4680' WITH 2 SX CMT. 1ST PLUG AT 1306' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 371' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4731	4742		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

10/28/15 ckm

District: 01

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 15 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
OCT 12 2015
KCC DODGE CITY

Form CP-2/3