

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21598-00-00
Spot: SESENW Sec/Twnshp/Rge: 1-26S-19W
3031 feet from S Section Line, 2970 feet from E Section Line
Lease Name: LEWIS TRUST "E" UNIT Well #: 1-1
County: EDWARDS Total Vertical Depth: 4720 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4642		WITH 2 SX CMT
PROD	4.5	4718	1635	WITH 125 SX CMT
SURF	8.625	273		WITH 325 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/08/2015 12:30 PM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1300' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 10/08/2015 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4642' WITH 2 SX CMT. 1ST PLUG AT 1289' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 297' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4692	4704		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICE.

Plugged through: CSG

10/28/15CKM

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT - 9 2015
KCC DODGE CITY