

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-00525-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 35-30S-33W  
2785 feet from S Section Line, 2504 feet from E Section Line  
Lease Name: LIGHT Well #: 1-35  
County: HASKELL Total Vertical Depth: 2760 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 1200  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1650		WITH 10 SX CMT
PROD	5.5	2767	0	WITH 700 SX CMT
SURF	8.625	692		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/13/2015 3:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: LEONEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2015 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 1650' WITH 10 SX CMT. TEST CASING TO 500#. HOLDING. RUN CBL FROM 700' TO 50'. FOUND TOP OF GOOD CMT AT 510' WITH CMT STRINGERS UP TO 210'. RUN TBG TO 750' & CIRCULATE CMT TO SURFACE WITH 75 SX CMT PUMP 10 SX CMT DOWN THE ANNULUS & PRESSURE TO 500#. HOLDING. TOOH WITH TBG & TOP OFF CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2742	2760	OH	
2629	2731		

KCC WICHITA  
OCT 26 2015  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

10/28/15 CKM

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
OCT 16 2015  
KCC DODGE CITY