

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-10134-00-01
Spot: SWNE Sec/Twnshp/Rge: 24-30S-34W
3302 feet from S Section Line, 1999 feet from E Section Line
Lease Name: R B GARNER Well #: 2
County: HASKELL Total Vertical Depth: 5603 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		875		
CIBP		1750		
CIBP		5000		
DVT		4850		WITH 200 SX CMT
PROD	5.5	5600	0	WITH 375 SX CMT
SURF	8.625	778		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/07/2015 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG AT 3500' WITH 20 SX CMT. CIBP @ 1750'. PERFORATE 4 HOLES AT 1730'. CMT RETAINER AR 1600'. PUMP 50 SX CMT. CIBP AT 875' OVER CSG LEAK. PERFORATE AT 815'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2015 7:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK AT 3500'. PLUG AT 3500' WITH 20 SX CMT. CIBP @ 1750'. PERFORATE AT 1730'. SET CMT RETAINER AR 1603'. STING IN TO RETAINER & SQUEEZE PERFS WITH 50 SX CMT. STING OUT OF RETAINER & CAP WITH 15 SX CMT. SET CIBP @ 875'. PERFORATE AT 813' WITH 275 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5560	5563		
4882	4908		
4732	4738		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
OCT 14 2015
KCC DODGE CITY

Signed [Signature] 10/28/15 CKM
(TECHNICIAN)