

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21777-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 1-10S-22W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BIDEN Well #: 1  
County: GRAHAM Total Vertical Depth: 3920 feet

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S BROADWAY STE 360  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3925		150 SX
SURF	8.625	247		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2015 10:00 AM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: JOHN DRISCOLL Company: MID-CONTINENT ENERGY CORP Phone: (785) 483-6446

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls. Perforations at 3756' - 3748', 3844' - 3850'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2015 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 240', 995', 1797' and 2500'  
Ran tubing to 3650' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2250' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 1250' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 20 sx cement. Tied on to backside and squeezed with 80 sx cement and 150 # hulls.

GPS: 39.20962 -099.72012

Perfs:

Top	Bot	Thru	Comments
3850	3844		
3756	3748		

KCC WICHITA  
OCT 26 2015  
RECEIVED

Remarks: QUALITY CEMENT TICKET # 1044

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

  
(TECHNICIAN)

10/28/15 CKM

CM

OCT 01 2015