

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24312-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 3-19S-24W
952 feet from S Section Line, 2306 feet from E Section Line
Lease Name: MCDONALD B Well #: 1-3
County: NESS Total Vertical Depth: 4470 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1617		WITH 215 SX CMT
PROD	4.5	4460	0	WITH 175 SX CMT
SURF	8.625	207		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2015 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS, THEN SPACER TO 1650' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2015 10:10 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO CASING & PUMPED 35 SX CMT & 150# HULLS, 40 BBL SPACER TO 1650' & 145 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 200#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4348	4388		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

10/28/15 CKM

District: 01

Signed Michael Maier
SM (TECHNICIAN)

RECEIVED
OCT 12 2015
KCC DODGE CITY