

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22434-00-00
Spot: SWSENWSW Sec/Twnshp/Rge: 13-24S-15W
1342 feet from S Section Line, 4355 feet from E Section Line
Lease Name: ENGLISH-REID Well #: 8
County: STAFFORD Total Vertical Depth: 4375 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, LL
Address: PO BOX 164
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4205		WITH 2 SX CMT
PROD	5.5	4374	0	WITH 125 SX CMT
SURF	8.625	597		WITH 250 SX CMT

Well Type: SWD UIC Docket No: E19845.2 Date/Time to Plug: 09/30/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PRESTON DREILING Company: NORTHERN LIGHTS OIL COMPAN Phone: (785) 639-2099

Proposed
Plugging
Method:

SET CIBP @ 4216' WITH 2 SX CMT. PERFORATE AT 990' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
Date/Time Plugging Completed: 10/01/2015 1:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

9/30/15: SET CIBP @ 4205' WITH 2 SX CMT. PERFORATED AT 990'. PUMPED 250 SX CMT. HAD MINIMAL CIRCULATION. CMT DID NOT REACH SURFACE. SHUT WELL IN. 10/1/15: TAGGED TOC @ 175'. HOOKED UP TO BACKSIDE & PUMPED 9 SX CMT. HELD AT 300 PSI. TOPPED OFF 5 1/2" WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4266	4274		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

10/28/15 CKM

District: 01

Signed Larry D Harris ECR5
(TECHNICIAN)

5A

Received
KANSAS CORPORATION COMMISSION

RECEIVED
OCT - 7 2015
KCC DODGE CITY

OCT 15 2015
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

UIC ✓