

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-06593-00-00
Spot: N2S2NW Sec/Twnshp/Rge: 5-12S-17W
3630 feet from S Section Line, 3960 feet from E Section Line
Lease Name: CLINTON Well #: 2
County: ELLIS Total Vertical Depth: 3659 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3615	1630	125 SX
SURF	8.625	1345		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-6964

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 900 # hulls.
Perforations - 2800' - 3452' LKC 3659' Arb.
CIBP - 2890'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2015 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

10/12/2015- 8:30AM Knocked out CIBP at 2890'. Cleaned out hole.
10/13/2015- Ran in hole with tubing to 3200'. Rigged to tubing and pumped 12 sx gel followed by 125 sx cement w/300 # hulls mixed in. Pulled tubing. Rigged to 5 1/2" casing for stretch. Cut casing at 1630'. Pumped 125 sx cement w/200 # hulls mixed in. Pulled casing to 1350' and pumped 50 sx cement w/100 # hulls mixed in. Pulled casing to 800' and pumped 100 sx cement w/200 # hulls mixed in. Pulled casing to 150' and pumped 55 sx cement to circulate cement to surface. Pulled casing. Hole standing full.

GPS: 39.04050 -099.23715

Perfs:

Top	Bot	Thru	Comments
3615	3659		
3434	3452		


KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: QUALITY WELL SERVICE INC. TICKET # 6120

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

10/28/15 CKM

CM

OCT 14 2015

OCT 14 2015