

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20255-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 2-1S-38W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: O BRIEN Well #: 1-D
County: CHEYENNE Total Vertical Depth: 4560 feet

Operator License No.: 3152
Op Name: POE SERVICING INC
Address: PO BOX 115
OBERLIN, KS 67749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4533		
SURF	8.625	171		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2015 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: RUBY POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 450 sx common cement and 500 # hulls.
8 5/8" surface casing set at 171' w/200 sx cement. 4 1/2" production casing set at 4533' w/235 sx cement.
TD 4560', PBTD 4533'. Perforations: 4413' - 4417', 4224' - 4232', 4038' - 4040', 4034' - 4036'.
Casing holes from 2600' - 1000'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2015 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran perforating tool to 3040' and shot 2 holes. Tool became lodged in casing at 2785' and parted line. Perforating tool could not be dis-lodged. Contacted supervisor for instruction. Decision to plug from 2780'. Ran tubing to 2780' and pumped 70 sx cement. Shut down until 10/09/15.
10/09/15- Ran tubing to 851', contacting bridge. Pulled tubing to surface. Tubing plugged with sand. Ran 6' perforated sub with 3/4 holes to 535'. Pumped 70 sx cement losing circulation after 50 sx cement. Pulled tubing to surface. Connected to 8 5/8" surface casing and pumped 35 sx cement. Shut down for weekend at 5:30 pm.
10/12/15- Tagged cement with tubing at 410' and pumped 25 sx cement. Circulated cement to surface. Pulled tubing to surface and topped 4 1/2" casing with 3 sx cement. Connected to 8 5/8" surface casing and pumped 2 sx cement. Pressured to 300 psi. Plug complete
GPS: 39.98930N -101.55968W

Perfs:

Top	Bot	Thru	Comments
4413	4417		
4224	4232		
4038	4040		
4034	4036		

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: POE SERVICING INC. COMPANY TOOLS

Plugged through: TBG

10/28/15 ckm

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM