

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24718-00-00
Spot: NENENE Sec/Twnshp/Rge: 29-19S-14W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: ALDRICH Well #: 1
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2028	1410	150 SX
SURF	8.625	864		425 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/25/2015 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ROBIN L AUSTIN Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1410'. Pulled casing to 1400' and pumped 100 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 140 sx cement. Pulled casing and hole stayed full.
GPS: 38.37529 -098.88640

Perfs:

Top	Bot	Thru	Comments
1736	1870		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

10/28/15 ckm

CM

Received
KANSAS CORPORATION COMMISSION

OCT 01 2015

OCT 15 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS