

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-00741-00-01  
Spot: NESENE Sec/Twnshp/Rge: 29-19S-14W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ALDRICH Well #: 2 OWWO  
County: BARTON Total Vertical Depth: 2051 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2028	1430	150 SX
SURF	8.625	864		425 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2015 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ROBIN L AUSTIN Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1430'. Pulled casing to 1425' and pumped 100 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/200 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface w/125 sx cement. Pulled casing and hole stayed full.

GPS: 38.37168 -098.88631

Perfs:

Top	Bot	Thru	Comments
1733	1866		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

10/28/15 CKM

CM

SEP 30 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 15 2015

CONSERVATION DIVISION  
WICHITA, KS