

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22431-00-01
Spot: N2NWSENE Sec/Twnshp/Rge: 1-7S-21W
3730 feet from S Section Line, 990 feet from E Section Line
Lease Name: TREXLER Well #: 2
County: GRAHAM Total Vertical Depth: 3670 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3664		125 SX
SURF	8.625	216		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2015 8:30 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: TOMMY ATKINS Company: RICHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2015 1:45 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

DV Tool set at 1774' and circulated cement to surface by Allied Cementing. No need to perforate. Ran tubing to 3500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1985' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 500' and pumped 35 sx cement. Circulated cement to pit. POOH. Hooked to the braden head and pumped 6 sx cement at 250 psi. Shut in. Topped off casing w/6 sx cement. Casing stayed full.

GPS: 39.47676 -099.60531

Perfs:

Top	Bot	Thru	Comments
3474	3477		
3453	3456		
3434	3438		
3398	3402		

Remarks: CONSOLIDATED CEMENTING TICKET # 49510

Plugged through: TBG

10/28/15 ckm

District: 04

Signed Ray AO in KCC

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

OCT 01 2015

OCT 15 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS