

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20365-00-01
Spot: SWSW Sec/Twnshp/Rge: 24-33S-30W
678 feet from S Section Line, 4664 feet from E Section Line
Lease Name: SHINOGL Well #: 1-24
County: MEADE Total Vertical Depth: 5910 feet

Operator License No.: 32126
Op Name: ROBERTS, GERALD M. DBA SUNFIRE E
Address: 701 S PARKWAY BLVD PO BOX 1761
LIBERAL, KS 67901

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4690		WITH 2 SX CMT
CIBP		5165		WITH 2 SX CMT
CIBP		5690		WITH 2 SX CMT
CIBP		5890		
COND	20	47		WITH 6 SX CMT
PROD	4.5	5909	2519	WITH 125 SX CMT
SURF	8.625	1481		WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/08/2015 12:00 PM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES LLC Phone: (620) 629-3131

Proposed Plugging Method: CIBP @ 5690' WITH 2 SX CMT. CIBP @ 5165' WITH 2 SX CMT. PLUG AT 1520' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 10/08/2015 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5690' WITH 2 SX CMT. CIBP @ 5165' WITH 2 SX CMT. 1ST PLUG AT 1520' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5810	5814		
5740	5774		
5215	5221		
3232	3234		
3228	3228		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED
OCT 14 2015
KCC DODGE CITY

Signed

[Signature]

(TECHNICIAN)

10/28/15 cem