

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21649-00-00
Spot: N2NESENW Sec/Twnshp/Rge: 20-23S-19W
3795 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HXP1 Well #: 4
County: EDWARDS Total Vertical Depth: 4775 feet

Operator License No.: 30337
Op Name: SPECIAL ENERGY CORP.
Address: PO DRAWER 369
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2490		WITH 2 SX CMT
CIBP		3950		
CIBP		4030		
CIBP		4200		
PROD	5.5	4300	0	WITH 325 SX CMT
SURF	8.625	860		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/01/2015 1:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: NATHAN WOOD Company: COPELAND ACID & CEMENT, INC. Phone: _____

Proposed Plugging Method: CIBP @ 2460' WITH 2 SX CMT. PERFORATE AT 900' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 10/01/2015 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2490' WITH 2 SX CMT. PERFORATED AT 900' & CIRCULATED CMT TO SURFACE WITH 240 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4216	4218		
4208	4211		
4043	4046		
3972	3976		
2514	2520		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

OCT 15 2015

CONSERVATION DIVISION
WICHITA, KS

10/28/15 *cm*

District: 01

RECEIVED
OCT - 7 2015
KCC DODGE CITY

Signed

JA

Eric MacLaren

(TECHNICIAN)