

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21182-00-01
Spot: SW Sec/Twnshp/Rge: 25-31S-32W
1315 feet from S Section Line, 4009 feet from E Section Line
Lease Name: MCCOY Well #: 2-25
County: SEWARD Total Vertical Depth: 5905 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2950		WITH 2 SX CMT
CIBP		4470		WITH 2 SX CMT
CIBP	4.5	5470		
COND	20	40		
PROD	4.5	5905	0	WITH 650 SX CMT
SURF	8.625	1712		WITH 725 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2015 10:30 AM
Plug Co. License No.: 32722 Plug Co. Name: KERR WELL SERVICE, INC.
Proposal Rcvd. from: TYSON DILKA Company: STELBAR OIL CORPORATION Phone: (970) 539-9354

Proposed Plugging Method: CIBP @ 5380' WITH 2 SX CMT. CIBP @ 2950' WITH 25 SX CMT. TBG AT 1740' CIRCULATE TO SURFACE. TIE ONTO ANNULUS & SQUEEZE CMT & PERSSURE UP.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2015 1:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 4470' WITH 2 SX CMT. CIBP @ 2950' WITH 2 SX CMT. TBG AT 1740'.
CIRCULATED WITH 100 SX CMT. BACKSIDE WAS FULL. TOPPED OFF WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5470	5470		
5439	5443		

KCC WICHITA
OCT 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY

Plugged through: TBG


10/28/15 CKM

District: 01

RECEIVED
OCT 14 2015
KCC DODGE CITY



Signed



(TECHNICIAN)