

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-20708-00-02  
Spot: NWSWSESW Sec/Twnshp/Rge: 3-31S-8E  
562 feet from S Section Line, 3827 feet from E Section Line  
Lease Name: DENTON Well #: 12  
County: ELK Total Vertical Depth: 2682 feet

Operator License No.: 3359  
Op Name: T & R OIL COMPANY, A GENERAL PA  
Address: PO BOX 92  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2024		50 SX
SURF	8.625	206		85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2015 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: ROGER PATTESON Company: \_\_\_\_\_ Phone: (620) 647-3352

Proposed Plugging Method: Gel hole, spot 10 sacks of cement at bottom, spot 5 sacks at 1300 feet, then cement from 550 feet to surface. Well has previously been cemented on outside of 4 1/2.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 09/17/2015 1:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1950' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 75 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1916	1924		
RECEIVED KCC DIST # 3 OCT 20 2015 CHANUTE, KS DS			


KCC WICHITA  
OCT 23 2015  
RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

10/28/15 CKM