

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25063-00-00
Spot: NESENW Sec/Twnshp/Rge: 28-17S-13W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: WAYNE Well #: 4
County: BARTON Total Vertical Depth: 3455 feet

Operator License No.: 33406
Op Name: THOMAS GARNER, INC.
Address: 305 E 7TH
ST JOHN, KS 67576

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3450	2215	200 SX
SURF	8.625	906		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TOM GARNER Company: THOMAS GARNER INC. Phone: (620) 793-3402

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 2215'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 95 sx cement. Pulled casing and hole stayed full.

GPS: 38.54618 -098.76717

Perfs:

Top	Bot	Thru	Comments
3450	3455		

KCC WICHITA
OCT 26 2015
RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

10/28/15 CKM

CM

OCT 14 2015