

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23747-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 1-22S-12W  
1909 feet from S Section Line, 2172 feet from E Section Line  
Lease Name: HELMERS Well #: 1-1  
County: STAFFORD Total Vertical Depth: 3710 feet

Operator License No.: 33483  
Op Name: VALHALLA EXPLORATION LLC  
Address: 8100 E 22ND ST N BLDG 1800-2  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3706	2358	WITH 175 SX CMT
SURF	8.625	582		WITH 450 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2015 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3436' WITH 5 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/08/2015 10:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SAND BACK TO 3420' WITH 5 SX CMT. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3506	3524		
3499	3504		
3486	3486		

KCC WICHITA  
OCT 20 2015  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA NEED FL\*\* USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

10/28/15 CKM

District: 01

Signed Gary Siderer  
(TECHNICIAN)

RECEIVED  
OCT 16 2015  
KCC DODGE CITY