

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05504-00-00
Spot: SESWNW Sec/Twnshp/Rge: 20-11S-17W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HADLEY A Well #: 6
County: ELLIS Total Vertical Depth: 3524 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3388		130 SX
PROD	5.5	3524		125 sx
SURF	10.875	1140		500 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM BERENS Company: WMKS ENERGY RESOURCES Phone: (785) 639-5727

Proposed Plugging Method: 09/14/2015- Ordered 100 sx common 4% cc.
09/15/2015- Ordered 100 sx common 5% cc.
09/16/2015- Ordered 100 sx common 5% cc.
4 1/2" retainer 1285 knocked out to 1500'.
Port Collar at 1828' w/175 sx cement.
Casing leaks at 1300' - 1330'
PBTD at 3300' CIBP

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2015 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

09/14/2015- Express ran in hole with tubing. Tagged retainer and pulled to 1490'. Quality rigged to tubing, mixed and pumped 50 sx common 4% cc and displaced out of tubing. Pulled tubing.
12:00pm- Ran in hole to 1490' and pumped 50 sx common 4% cc. Hard vacuum on well.
09/15/2015- 9:00am- Ran in hole and tagged cement at 1480'. Pumped 50 sx common 5% cc. Pulled tubing and left set for 2 hours.
12:30pm- Ran in hole and tagged cement at 1480'. Pumped 40 bbl of drilling mud followed by 50 sx cement w/5% cc.
09/16/2015 - Tagged cement at 400'. Rigged to ^{tubing} 4 1/2" casing and pumped 40 sx common cement w/4% cc to circulate cement to pit. Pulled tubing. Dug out backside. Rigged to 4 1/2" casing and topped off with 10 sx cement. Rigged to 4 1/2" liner between 4 1/2" and 5 1/2" casing. Pumped 10 sx cement with 200 psi. Shut in pressure 200 psi. Rigged to 10 3/4" casing and pumped 50 sx cement w/150 psi. Blew a small hole in head. No shut in pressure.
GPS: 39.28310 -099.23771

Perfs:


Remarks: QUALITY CEMENTING CO TICKET #S 1037, 1038 AND 1040

Plugged through: TBG

10/28/15 CKM

District: 04

Signed _____



(TECHNICIAN)

CM

SEP 17 2015

Received
KANSAS CORPORATION COMMISSION

OCT 15 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS