

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22819-00-01
Spot: NENWNWSE Sec/Twnshp/Rge: 30-26S-13E
2540 feet from S Section Line, 2098 feet from E Section Line
Lease Name: BAKER Well #: 1
County: GREENWOOD Total Vertical Depth: 1715 feet

Operator License No.: 32960
Op Name: YUKON PROPERTIES LLC
Address: 9910 BIRCHDALE AVE
DOWNEY, CA 90240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1715		0 SX
SURF	7.5	20		0 SX

Well Type: EOR UIC Docket No: E26104.1 Date/Time to Plug:
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TERRY CARROLL Company: CARROLL ENERGY Phone: (800) 917-1618

Proposed Plugging Method: spot 5 sacks of cement at td, 5 sacks of cement at the top of oswego 1250 ft, cement 350 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2015 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Operator ran 2-3/8" tubing down 4-1/2" casing to 1650', ran 2 sacks gel, spotted 5 sacks portland cement, pulled tubing to 1250' spotted 5 sacks portland cement, pulled tubing to 350' circulated portland cement to surface, pulled tubing out topped off well with portland cement. Used 60 sacks portland cement to plug well. Consolidated Oil Well Services was pumping contractor.

Perfs:

Top	Bot	Thru	Comments
1659	1663		

RECEIVED
KCC DIST #3
OCT 19 2015
CHANUTE, KS
JA

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)

10/28/15 CKM