

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-151-00344-0000

FILE NO. 44-22

LOCATION SW-50-7E

SEC. 11 TWP. 26 RGE. 15-W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Long

Operator Anderson-Richard Oil Corp Address Box # 142 - H. Bond - Kans.

Field _____ County Peott

Total Depth 4153 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 370 ft - Circulated with cement.
5 1/2" casing set at 4150 ft - 125 sacks of cement.
Plugged back to 3840 ft. with sand - Pumped 5 sacks of
cement at 3840 ft. Shot off & pulled the 5 1/2" casing - mud
to 300 ft. Set rock bridge & 10 sacks of cement at 300 ft -
Mud to 25 ft. Bridge & 10 sacks of cement
at the snubber.
Forbes Casing Pulling Co - Plugging Contractors

PLUGGING
FILE SEC. 11 T. 26 R. 15 W
BOOK PAGE 44 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1952
CONSERVATION DIVISION
Wichita, Kansas

C. H. Stough
District Conservation Agent
Date 9-19-52