

1040957 4-26 API NUMBER 15- 047-20,480 -0000
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION Irr. Sec., SEC. 4, T 26 S, R 16 W/E
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License / 5056
Operator: F.G. Holl Company L.L.C.
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167
Lease Name: Cudney A Well / 1
County: Edwards
Well Total Depth: 4505 146.41 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor: Pratt Well Service License Number 5893
Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 26 Month: 4 Year: 19 95
Plugging proposal received from: Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4500' w/200 sx cement, PBTD 4435', Perfs at 4388-92, 4420-24'
1st plug sand back to 4320' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Plugging Proposal Received by: Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1 p.m. Day: 26 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 4 sx cement on top of sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement. No wiper plug-swedged back.
Maximum pressure 50 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2342' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not observe) this plugging.
DATE 5-2-95
INV. NO. 42725

Signed: Stephen J. Pfeifer (TECHNICIAN)

KANSAS CORPORATION COMMISSION
RECEIVED
MAY 07 1995
CONSERVATION DIVISION
WICHITA, KS