

To: 1 090759  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 047-20,537 -0000  
SE NW SE, SEC. 4, T 26 S, R 16 W X  
1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9449  
Operator: Great Eastern Energy  
Name & Address: 5990 Greenwood Plaza Blvd. #116  
Englewood, CO 80111-4708

Lease Name Parker Well # 4  
County Edwards 143.94  
Well Total Depth 4429 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 21 Month: 11 Year: 19 96

Plugging proposal received from Bill Reed  
(company name) Great Eastern Energy (phone) 316-653-2277

Work: 5 1/2" at 4427' w/150 sx cement, PBTD 4140', Perfs at 4065-70'  
1st plug sand back to 4015' and dump 5 sx cement on top of sand through bailer,  
2nd plug spot 10 sx gel and 40 sx cement at 2100',  
3rd plug pull to 1050' and spot 10 sx gel and 50 sx cement,  
4th plug pull to 480' and spot 50 sx cement, 5th plug top off with 10 sx cement at 40'.

1996 NOV 25 P 11:25  
SANSAP, ODP  
FILED

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 p.m. Day: 21 Month: 11 Year: 1996


ACTUAL PLUGGING REPORT 1st plug sanded back to 4015' and dumped 5 sx cement on top of sand through bailer,

2nd plug spotted 10 sx gel and 40 sx cement at 2100',  
3rd plug pulled to 1050' and spotted 10 sx gel and 50 sx cement,  
4th plug pulled to 480' and spotted 50 sx cement,  
5th plug topped off with 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I did/did not observe this plugging.

DATE NOV 26 1996  
INV. NO. 47053

Signed  (TECHNICIAN)