

To: 1 040583  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-22

API NUMBER 15- 047-20,538-0000 247  
SE NE SE, SEC. 4, T. 26 S, R. 16 W/E  
1650 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992  
Operator: Patton Oil Company  
Name & Address 672 W. 4th St.  
Hoisington, KS 67554

Lease Name Parker Well # 5  
County Edwards 144.39  
Well Total Depth 4443 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 22 Month: 10 Year: 19 91

Plugging proposal received from Bill Reed  
(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4434' w/125 sx cement, Open hole 4434-4443'  
1st plug sand back to 4380' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 22 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4384' and dumped 5 sx cement on top of sand  
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2313' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did / did not) observe this plugging.  
DATE 11-14-91  
INV. NO. 33710

STATE CORPORATION COMMISSION

OCT 29 1991

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas