

To: 1 040584
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-22

API NUMBER 15-047-20,566-0000 248
NW NE SE, SEC. 4, T. 26 S, R. 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992
Operator: Patton Oil Company
Name & Address 672 W. 4th St.
Hoisington, KS 67554

2310 feet from S section line
990 feet from E section line

Lease Name Parker Well # 6
County Edwards 144.17
Well Total Depth 4436 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 444

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 22 Month: 10 Year: 19 91

Plugging proposal received from Bill Reed
(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4431' w/125 sx cement, Open hole 4431-36'
1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 22 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4381' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2410' of 5 1/2" casing.
(If additional description of circumstances necessary, use BACK of this form.)

INVOICED
DATE 11-16-91
INV. NO. 33711

OCT 29 1991
10-29-91
Conservation Division
Wichita, Kansas

Signed Stephen J. Pfeifer
(TECHNICIAN)