

To: 1 040585
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-22 API NUMBER 15-047-20,567-0000 243

NW NW SE, SEC. 4, T. 26 S, R. 16 W

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Parker Well # 7

Operator: Patton Oil Company

County Edwards 144.04

Name & Address 672 W. 4th St.

Well Total Depth 4432 feet

Hoisington, KS 67554

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 434'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 22 Month: 10 Year: 1991

Plugging proposal received from Bill Reed

(company name) Patton Oil Company (phone) 316-653-2277

was: 5 1/2" at 4432' w/125 sx cement, 'PBSD 4422', Perfs at 4395-99'

1st plug sand back to 4345' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 22 Month: 10 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 4345' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2536.9' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

observe the STATE PLUGGING COMMISSION

DATE 11-14-91

OCT 29 1991
10-29-91
CONSERVATION DIVISION
Wichita Kansas

Signed Steve Pfeifer
(TECHNICIAN)

INVOICED

RECEIVED

INV. NO. 33708