

To: 1 040586
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-22
API NUMBER 15- 047-20,568-0600 244
NW SW SE, SEC. 4, T. 26 S, R. 16 W/BL

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

990 feet from S section line
2310 feet from E section line

Operator: Patton Oil Company

Lease Name Parker Well # 8

Name & Address 672 W. 4th St.

County Edwards 144.10

Hoisington, KS 67554

Well Total Depth 4434 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 a.m. Day: 22 Month: 10 Year: 19 91

Plugging proposal received from Bill Reed

(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4432' w/125 sx cement, PBSD 4125', Perfs at 4071-76'

1st plug sand 5 1/2" casing back to 4020' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:15 a.m. Day: 22 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4021' and dumped 5 sx cement on top of sand
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 150 psi and shut in 0 psi. Well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2016.4' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED STATE CORPORATION COMMISSION
(I did not observe this plugging.)

DATE 11-14-91

OCT 29 1991

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 33712

CONSERVATION DIVISION
Wichita, Kansas