

1 061043

12-8-87 15-047-20569.0000

API NUMBER 15- Drill completion date 11/21/79

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SW, SEC. 4, T 26 S, R 16 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Parker Well # 9

Operator: Patton Oil Company

County Edwards 145.34

Name & Address 672 West 4th Street

Well Total Depth 4472 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 447

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4471' PBTD 4464' Top perf at 4434'

1st plug sand back to 4380' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 a.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 120 sx cement.

STATE CORPORATION COMMISSION
12-11-87
DEC 11 1987

Maximum pressure 400 psi and shut in 200 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2389' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 12-14-87

Signed Paul A. Luttie (TECHNICIAN)

INV. NO. 19262