

10-3

To: 1 120137  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,582-000  
SE SE NE, SEC. 4, T 26 S, R 16 W/E  
2660 feet from S section line  
392 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5142  
Operator: Sterling Drilling Company  
Name & Address: Box 129  
Sterling, KS 67579

Lease Name Cudney "B" Well # 3-4  
County Edwards 147.71  
Well Total Depth 4545 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well  Gas Well  Input Well  SHD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 3 Month: 10 Year: 19 88

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457  
were: 4 1/2" at 4523' PBTD 4135' Perfs at 4082-86'

1st plug sand back to 4030' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-7-88  
OCT 7 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging operations attended by Agent?: All  Part  None   
Operations Hour: 1:30 p.m. Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 4 sx cement on top of  
sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2400' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 10-10-88  
REL. NO. 22567

Signed Dean Rankin  
(TECHNICIAN)