

To: 1 061170  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-6  
API NUMBER 15-047-20,589-0000  
SE SE NE, SEC. 4, T 26 S, R 16 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Operator: Sterling Drilling Company  
Name &  
Address Box 129  
Sterling, KS 67579

3170 feet from S section line  
320 feet from E section line

Lease Name Cudney "B" Well # 4-4  
County Edwards 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 6 Month: 12 Year: 19 88

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4577' Perfs at 4464-68' & 4466-70'

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1988 12-9-88

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: CONSERVATION DIVISION  
Wichita Kansas Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 6 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 4 sx cement on top of  
sand through bailer.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 120 sx cement.

Maximum pressure 250 psi and shut in 120 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2411' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 12-12-88

23828

Signed Paul A. Luthi  
(TECHNICIAN)