

10-3

1 120139

API NUMBER 15-047-20,592-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NE, SEC. 4, T 26 S, R 16 W&E

2980 feet from S section line

960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Cudney "B" Well # 5-4

Operator: Sterling Drilling Company

County Edwards 147.88

Name & Address Box 129

Well Total Depth 4550 feet

Sterling, KS 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 3 Month: 10 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4533' Perfs at 4434-38'

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and dump 120 sx cement.

STATE CORPORATION COMMISSION 10-7-88

OCT 7 1988 Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-800 psi, shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2400' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

Signed Dennis Ruckel
(TECHNICIAN)

DATE 10-10-88

INV. NO. 22568