

040961 5-2
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-20,595 -0000
Irreg. sec SEC. 4, T 26 S, R 16 W/E
1140 feet from NXK section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company L.L.C.
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Cudney A Well # 2
County Edwards 147.39
Well Total Depth 4535 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 482

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address: P.O. Box 847, Pratt, KS 67214

Company to plug at: Hour: 12:15 p.m. Day: 2 Month: 5 Year: 1995

Plugging proposal received from Tom Pool

(company name) F.G. Holl Company (phone) 316-995-3171

Work: 4 1/2" at 4533' w/175 sx cement, PBD 4430', Perfs at 4388-90, 4415-17'

1st plug sand back to 4320' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 P. Day: 2 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2278' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 5-16-95
INV. NO. 42828

RECEIVED
STATE CORPORATION COMMISSION
5-4-95
MAY 04 1995
SIGNED Stephen J. Pfeifer (TECHNICIAN)