

12-8-87 15-047-20693-0000

To: 1 061042
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 7/19/80
NE SE SW, SEC. 4, T 26 S, R 16 W/E
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992
Operator: Patton Oil Company
Name & Address: 672 West 4th Street
Hoisington, KS 67544

Lease Name Parker Well # 10
County Edwards 147.45
Well Total Depth 4537 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 467

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4536' PRTD 4519' Top perf at 4409'

1st plug sand back to 4480' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Ricahrd Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
12-11-87
DEC 11 1987

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2313' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLCED

(did / did not) observe this plugging.

DATE 12-14-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 19264