

To: 1 061044  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-8-87 15-047-20654-0000  
API NUMBER 15-Drill completion date 10/16/87

SE SW SW, SEC. 4, T 26 S, R 16 W/E  
330 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Parker Well # 11

Operator: Patton Oil Company

County Edwards 145.08

Name & Address 672 West 4th Street

Well Total Depth 4464 feet

Hoisington, KS 67544

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 462

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4462' PBD 4470' Open hole from 4464-4470'

1st plug sand back to 4410' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:15 p.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
12-11-87  
DEC 11 1987

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2271' of 5 1/2" casing. Kansas  
(If additional description is necessary, use BACK of this form.)

INVOICED  
did observe this plugging.

Signed Paula Luthi (TECHNICIAN)

DATE 12-14-87

INV. NO. 19266