

12-8-87 15-047-70655-0000

To: 1 061041  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion date 8/4/80  
NW SW SW, SEC. 4, T 26 S, R 16 W/R  
990 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5992  
Operator: Patton Oil Company  
Name & Address: 672 West 4th Street  
Hoisington, KS 67544

Lease Name Parker Well # 12  
County Edwards 146.61  
Well Total Depth 4511 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4510' PRTD 4465' Top perf at 4441'  
1st plug sand back to 4460' and dump 5 sx cement. on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:15 a.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4460' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

STATE CORPORATION COMMISSION  
DEC 11 1987  
12-11-87  
CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 12-14-87  
INV. NO. 19263

Signed Paul A. Luthi (TECHNICIAN)