

To: 1 051413
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-14 206 R
API NUMBER 13-047-20,670-0000
330' FNL, 330' FWL
S/2 Lot 2, SEC. 4, T 26 S, R 16 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142
Operator: Sterling Drilling Company
Name & Address: P.O. Box 129
Sterling, KS 67579

_____ feet from S section line
_____ feet from E section line
Lease Name Mayhew "A" Well # 2-4
County Edwards 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 14 Month: 3 Year: 1991

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4539' w/250 sx cement, Perfs at 4432-36'
1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer.
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 14 Month: 3 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 420 psi and shut in 122 psi

RECEIVED
STATE CORPORATION COMMISSION
3-20-91
MAR 20 1991

Remarks: Used 60/40 Pozmix, 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED (if necessary) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 4-3-91

INV. NO. 31313