

1040962 5-2  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 047-20,697-0000  
Irreg. sec. SEC. 4, T 26 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056  
Operator: F.G. Holl Company L.L.C.  
Name:  
Address P.O. Box 780167  
Wichita, KS 67278-0167

1230 feet from N & section line  
1650 feet from E section line  
Lease Name Cudney A Well # 3  
County Edwards 147.39  
Well Total Depth 4535 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well  Gas Well  Input Well  SMD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 2 Month: 5 Year: 19 95

Plugging proposal received from Tom Pool

(company name) F.G. Holl (phone) 316-995-3171

Work: 4 1/2" at 4534' w/250 sx cement, PBTD 4493', Perfs at 4428-32'

1st plug sand back to 4385' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:30 a.m. Day: 2 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4385' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
5-4-95  
MAY 04 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2437' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 5-16-95  
INV. NO. 42829

Signed *Stephen J. Pfeifer*  
(TECHNICIAN)