

1 080408

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,745-0000

NE SE NW, SEC. 4, T 26 S, R 16 W/EX

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Parker A Well # 2

Operator: Oil Producers Inc. of Kansas

County Edwards 146.09

Name & Address P. O. Box 8647, North Woodlawn

Well Total Depth 4495 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 299

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 am Day: 1 Month: August Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4494' PBD 4482' Perfs at 4444-56'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

orders given by Steve Durrant

Plugging Proposal Received by *J. H. Med* (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45 pm Day: 1 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Recovered 3011' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-14-85

INV. NO. 9607

STATE CORPORATION COMMISSION

Signed *J. H. Med* (TECHNICIAN)

AUG 13 1985 8-13-85