

To: 121030 5-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,750-0000
SE SW NW, SEC. 4, T. 26 S, R. 16 WXE
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893
Operator: Pratt Well Service Inc.
Name & Address P.O. Box 847
Pratt, KS 67124

Lease Name Guggins Well # 1
County Edwards
Well Total Depth 4530 147.23 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:30 p.m. Day: 16 Month: 5 Year: 1995

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 5 1/2" at 4529' with 150 sx cement, Perfs at 4452-4462'

1st plug sand back to 50' above the perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1995 5-17-95

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 16 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)
I (and/or my agent) observe this plugging.

DATE JUN 13 1995

Signed Dennis Rankin
(TECHNICIAN)

WV. NO. 42959