

1 080407

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,776-6000

SW SE NW, SEC. 4, T 26 S, R 16 W/R

3135 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Parke^R A Well # 3

Operator: Oil Producers, Inc. of Kansas

County Edwards 146.58

Name & Address P. O. Box 8647 North Woodlawn,

Well Total Depth 4510 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 1 Month: August Year: 1985

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4509' PBD 4480' Perfs at 4446-66'

1st plug sand back to 4390' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Orders given by Steve Durrant

Plugging Proposal Received by J. A. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:10 pm Day: 1 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 3484'. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-14-85

INV. NO. 9606

8-1

AUG 13 1985

CONSERVATION DIVISION

Signed J. A. [Signature]
(TECHNICIAN)