

10-3

To: 1 120138
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-047-20,785-0000
SW NW NE, SEC. 4, T 26 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142
Operator: Sterling Drilling Company
Name & Address: Box 129
Sterling, KS 67579

app. 4290 feet from S section line
2370 feet from E section line
Lease Name Mayhew "A" Well # 3-4
County Edwards 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 445

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Kelso Casing Pulling, Inc. License Number 6050
Address: Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 3 Month: 10 Year: 19 88

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457
were: 4 1/2" at 4545' Perfs at 4431-35'

1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper pump 120 sx cement.

STATE CORPORATION COMMISSION

10-7-88

OCT 7 1988 Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging operations attended by Agent?: All Part None
Operations Completed: Hour: 11 a.m. Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-88
INV. NO. 22569

Signed [Signature] (TECHNICIAN)