

1-120540

3-11

212
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,803-0000
330' FSL, 330' FEL
S/2 Lot 3 NW, SEC. 4, T 26 S, R 16 W EX

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Mayhew "A" Well # 4-4

Operator: Sterling Drilling Company

County Edwards 148.20

Name & Address P.O. Box 129

Well Total Depth 4560 feet

Sterling, KS 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 11 Month: 3 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4550' w/225 sx cement, Perfs at 4440-44'

1st plug sand back to 4390' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 11 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4390' and dumped 4 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-225 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2437' of 4 1/2" casing. MAR 15 1991

(If additional description is necessary, use BACK of this form.)

INVOICED
I would like to observe this plugging.

Signed _____
(TECHNICIAN)

DATE 4-3-91

INV. NO. 31315