

1040966

5-5

API NUMBER 15- 047-20,818-0000

KANSAS CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

Irreg. sec SEC. 4, T 26 S, R 16 W/E

4860 feet from S section line

2300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cudney A Well # 4

Operator: F.G. Holl Company L.L.C.

County Edwards 147.55

Name & Address P.O. Box 780167

Well Total Depth 4540 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 441

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:45 p.m. Day: 5 Month: 5 Year: 19 95

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4532' w/275 sx cement, Perfs at 4076-80'

1st plug sand back to 3910' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 5 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3910' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

RECEIVED
KANSAS CORPORATION COMMISSION
5-8-95
MAY 08 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 5-16-95

INV. NO. 42832

Signed *Stephen J. Pfeifer* (TECHNICIAN)