

1 030970

8-17-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,830-000

SE SW SW, SEC. 4, T 26 S, R 16 W/E  
320 feet from S section line  
4380 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3521

Lease Name Turnbaugh Well # 1

Operator: Ranger Petroleum Corporation  
Name & Address: P.O. Box 1036  
Wichita, KS 67201

County Edwards 147.23

Well Total Depth 4530 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 17 Month: 8 Year: 19 88

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4524' PBTD 4524' Perfs at 4454-60'

1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1988  
CONSERVATION DIVISION  
WICHITA, KANSAS

8-23-88

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: 10:45 a.m. Day: 17 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT: 1st plug sanded back to 4400' and dumped 5 sx cement on top of

sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 50/50 Pozmix 4% gel by B.J. Titan. Recovered 2650' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 8-24-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 21905

8-17