

040969 5-5
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-047-20,836 -0000

Irreg. sec SEC. 4, T 26 S, R 16 W/E

330' FNL Lot 2 feet from S section line

330' FEL Lot 2 feet from E section line

Lease Name Cudney A Well # 5

County Edwards 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 440

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company L.L.C.

Name & Address P.O. Box 780167

Wichita, KS 67278-0167

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:45 p.m. Day: 5 Month: 5 Year: 19 95

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4545' w/275 sx cement, PBSD 4505', Perfs at 4452-56'

1st plug sand back to 4365' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 150, sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 p.m. Day: 5 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4365' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

RECEIVED KANSAS CORPORATION COMMISSION

MAY 08 1995

CONSERVATION DIVISION WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2230' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (to be used only) observe this plugging.

DATE 5-16-95

INV. NO. 42830

Signed [Signature] (TECHNICIAN)